

North Sea Link (NSL) Allocation Constraints - From Trial Operations (1 October 2021)

		Comments
Loss Factor	2.6%	700 MW capacity at Receiving End - loss factor of 2.6%. Sending End capacity will be 718 MW. This is an initial value and will be updated in line actual performance data and expected flows.
Ramping Limit (Sending End)	308 MW / hour	This is used in the Day Ahead auction to limit the hour to hour flow change on NSL.
Max operating Ramp Rate – Day Ahead	15 MW/min	